

# Demo Concrete Co.

mondogaglione@hotmail.com

# QUOTE

Quote # **312260CF**  
Date **June 14, 2026**  
Valid for **30 days**

## PREPARED FOR

---

Thank you for the opportunity to quote your project.

## Included in this quote

### MATERIALS

<b>Ready-mix concrete 30 MPa</b> 1160 sq ft @ 4" (incl. 10% waste)	12.25 m3
<b>Granular A</b> 4" compacted base (incl. 10% waste)	26.5 tonne
<b>Wire mesh 6x6 W2.9 (incl. 10% waste)</b>	1276 sqft
<b>Poly vapour barrier 6 mil (incl. 10% waste)</b>	1276 sqft

### LABOUR

<b>Foreman x 1</b> 2 days	16 hr
<b>Finisher x 1</b> 2 days	16 hr
<b>Labourer x 2</b> 2 days	32 hr

### EQUIPMENT

<b>Excavator</b> 1 day incl. mobilization	1 day
<b>Skid steer</b> 2 days incl. mobilization	2 day
<b>Plate tamper</b> 2 days incl. mobilization	2 day

### DISPOSAL

<b>Excavated soil disposal</b> 27.4 m <sup>3</sup> loose in 14 yd bins	3 bin
---	-------

Subtotal	\$13,362.81
Tax (13%)	\$1,737.17

**Total** **\$15,099.98**

## Notes

- Pricing includes labour, materials, and standard site cleanup.
- Concrete is 30 MPa unless otherwise specified.
- Valid for 30 days. Rock excavation, unsuitable subgrade, or changes to the work described above are billed as change orders.
- Payment terms: 50% deposit, balance due on completion.
- Concrete colour and minor surface variation are inherent to the material; weather and site conditions may affect the schedule.

## Thank you for your business.

Questions? [mondogaglione@hotmail.com](mailto:mondogaglione@hotmail.com)

---

**Demo Concrete Co.**