

Demo Concrete Co.

mondogaglione@hotmail.com

QUOTE

Quote # **35313853**
Date **June 16, 2026**
Valid for **30 days**

PREPARED FOR

Thank you for the opportunity to quote your project.

Included in this quote

MATERIALS

Ready-mix concrete 30 MPa 200 sq ft @ 5" (incl. 10% waste)	2.75 m3
Granular A 6" compacted base (incl. 10% waste)	7 tonne
Wire mesh 6x6 W2.9 (incl. 10% waste)	220 sqft
Poly vapour barrier 6 mil (incl. 10% waste)	220 sqft

LABOUR

Foreman x 1 1 day	8 hr
Finisher x 1 1 day	8 hr
Labourer x 2 1 day	16 hr

EQUIPMENT

Excavator 1 day incl. mobilization	1 day
Skid steer 1 day incl. mobilization	1 day
Plate tamper 1 day incl. mobilization	1 day
Power trowel 1 day incl. mobilization	1 day

DISPOSAL

Excavated soil disposal 6.5 m ³ loose in 14 yd bins	1 bin
--	-------

Subtotal	\$5,932.60
Tax (13%)	\$771.24

Total

\$6,703.84

Notes

- Pricing includes labour, materials, and standard site cleanup.
- Concrete is 30 MPa unless otherwise specified.
- Valid for 30 days. Rock excavation, unsuitable subgrade, or changes to the work described above are billed as change orders.
- Payment terms: 50% deposit, balance due on completion.
- Concrete colour and minor surface variation are inherent to the material; weather and site conditions may affect the schedule.

Thank you for your business.

Questions? mondogaglione@hotmail.com

Demo Concrete Co.