

Demo Concrete Co.

mondogaglione@hotmail.com

QUOTE

Quote # **9F8B5012**
Date **June 18, 2026**
Valid for **30 days**

PREPARED FOR

Thank you for the opportunity to quote your project.

Included in this quote

MATERIALS	
PT post 6x6 (8 ft) - 19 posts	19 each
Cedar fence board 1x6 - 6 ft high, 150 lf fence (approx 9 boards per 8 ft section x 19 sections)	1026 lf
Post concrete (2 bags per post x 19 posts)	38 each
Exterior screws (per box)	4 each
PT 2x4 rails (3 rails per bay x 19 bays x 8 ft)	456 lf
LABOUR	
Post installation - \$90 per post x 19 posts (contractor rate)	19 each
3 workers x 3 days x 8 hrs for board installation, rails, and finishing	72 hr
EQUIPMENT	
Post-hole auger - 3 days	1 day
Post-hole auger mobilization	1 each

Subtotal \$12,701.33
Tax (13%) \$1,651.17

Total \$14,352.50

Notes

- Pricing includes labour, materials, and standard site cleanup.
- Concrete is 30 MPa unless otherwise specified.
- Valid for 30 days. Rock excavation, unsuitable subgrade, or changes to the work described above are billed as change orders.
- Payment terms: 50% deposit, balance due on completion.
- Concrete colour and minor surface variation are inherent to the material; weather and site conditions may affect the schedule.

Thank you for your business.

Questions? mondogaglione@hotmail.com

Demo Concrete Co.