

# Demo Concrete Co.

mondogaglione@hotmail.com

# QUOTE

Quote # **CDC0CD9C**  
Date **June 14, 2026**  
Valid for **30 days**

## PREPARED FOR

Test 1

## PROJECT ADDRESS

123 Maple Ave

Thank you for the opportunity to quote your project.

## Included in this quote

### MATERIALS

**Ready-mix concrete 30 MPa** 10.5 m3  
800 sq ft @ 5" (incl. 10% waste)

**Granular A** 27.5 tonne  
6" compacted base (incl. 10% waste)

**Wire mesh 6x6 W2.9 (incl. 10% waste)** 880 sqft

### LABOUR

**Foreman x 1** 16 hr  
2 days

**Finisher x 1** 16 hr  
2 days

**Labourer x 2** 32 hr  
2 days

### EQUIPMENT

**Excavator** 1 day  
1 day incl. mobilization

**Skid steer** 2 day  
2 days incl. mobilization

**Plate tamper** 2 day  
2 days incl. mobilization

### DISPOSAL

**Excavated soil disposal** 3 bin  
26.0 m<sup>3</sup> loose in 14 yd bins

Subtotal \$12,573.20

Tax (13%) \$1,634.52

**Total \$14,207.72**

## Notes

- Pricing includes labour, materials, and standard site cleanup.
- Concrete is 30 MPa unless otherwise specified.
- Valid for 30 days. Rock excavation, unsuitable subgrade, or changes to the work described above are billed as change orders.
- Payment terms: 50% deposit, balance due on completion.
- Concrete colour and minor surface variation are inherent to the material; weather and site conditions may affect the schedule.

**Thank you for your business.**

Questions? [mondogaglione@hotmail.com](mailto:mondogaglione@hotmail.com)

---

**Demo Concrete Co.**