

Demo Concrete Co.

mondogaglione@hotmail.com

QUOTE

Quote #

DFFA0539

Date

June 16, 2026

Valid for

30 days

PREPARED FOR

Thank you for the opportunity to quote your project.

Included in this quote

MATERIALS

Ready-mix concrete 30 MPa 200 sq ft @ 5" (incl. 10% waste)	2.75 m3
--	---------

Granular A 6" compacted base (incl. 10% waste)	7 tonne
--	---------

Wire mesh 6x6 W2.9 (incl. 10% waste)	220 sqft
---	----------

Poly vapour barrier 6 mil (incl. 10% waste)	220 sqft
--	----------

LABOUR

Foreman x 1 1 day	8 hr
-----------------------------	------

Finisher x 1 1 day	8 hr
------------------------------	------

Labourer x 2 1 day	16 hr
------------------------------	-------

EQUIPMENT

Excavator 1 day incl. mobilization	1 day
--	-------

Skid steer 1 day incl. mobilization	1 day
---	-------

Plate tamper 1 day incl. mobilization	1 day
---	-------

Power trowel 1 day incl. mobilization	1 day
---	-------

DISPOSAL

Excavated soil disposal 6.5 m ³ loose in 14 yd bins	1 bin
--	-------

Subtotal	\$5,932.60
----------	------------

Tax (13%)	\$771.24
-----------	----------

Total

\$6,703.84

Notes

- Pricing includes labour, materials, and standard site cleanup.
- Concrete is 30 MPa unless otherwise specified.
- Valid for 30 days. Rock excavation, unsuitable subgrade, or changes to the work described above are billed as change orders.
- Payment terms: 50% deposit, balance due on completion.
- Concrete colour and minor surface variation are inherent to the material; weather and site conditions may affect the schedule.

Thank you for your business.

Questions? mondogaglione@hotmail.com

Demo Concrete Co.